


Best Water! Best Service!



## GARDNERVILLE WATER COMPANY WATER WATER MAIN LOWERING (G-15)



### TYPICAL CROSSING DETAIL

NOT TO SCALE

#### NOTES:

1. ALL POTABLE WATER CROSSINGS OF EXISTING OR PROPOSED UTILITIES, OR OTHER UNDERGROUND OBSTRUCTION SHALL BE DETAILED BY THE DESIGN ENGINEER, AND SHALL MEET THE CRITERIA OUTLINED BY NAC CHAPTER 445A AND GARDNERVILLE WATER COMPANY STANDARD DETAIL G-14. FOR PURPOSES OF SEPARATION AND PROTECTION OF THE WATER SUPPLY, RECLAIMED WATER SHALL BE CONSIDERED A SEWER LINE.
2. THE ENTIRE ASSEMBLY SHALL BE INSTALLED USING DUCTILE IRON RESTRAINED MECHANICAL JOINT FITTINGS.
3. UPON APPROVAL OF GARDNERVILLE WATER COMPANY, THE ABOVE ASSEMBLY MAY BE REPLACED WITH A WELDED STEEL "SPOOL" OF EQUIVALENT DIAMETER, PRIMED AND WRAPPED (10 MILS MIN.). CONNECT TO EXISTING LINES USING MECHANICAL JOINTS. STEEL SPOOL SHALL BE CONSTRUCTED BY A CERTIFIED WELDER AND PRESSURE CHECKED IN ACCORDANCE WITH SPECIFICATIONS.
4. CONCRETE AND REBAR FOR THRUST BLOCKS SHALL NOT INTERFERE WITH THE REMOVAL OF BOLTED ASSEMBLIES.
5. AN AIR-RELEASE WITH A POSITIVE GRADE FROM MAIN TO RELEASE, SHALL BE INSTALLED ON BOTH SIDES OF CROSSING (18 INCHES MINIMUM FROM ANY FITTING) UNLESS OTHERWISE NOTED ON THE APPROVED PLANS. ONE AIR-RELEASE MAY BE USED WITH ONE LINE TO EACH SIDE OF CROSSING.

NO.	REVISION	DATE	GARDNERVILLE WATER COMPANY - STANDARD DETAIL	DRAWING NO.
			<h1 style="margin: 0;">WATER MAIN LOWERING</h1>	<b>G-15</b>
				DATE: 09/22      PAGE: 15