


GARDNERVILLE WATER COMPANY COMBINATION AIR VALVE ASSEMBLY (G-11)

6" DIAMETER SCH. 40 STEEL BOLLARDS W/DOMED CONCRETE TOP - GROUTED SOLID WITH CONCRETE AND INSTALLED IN A TRIANGULAR PATTERN (2' SEPARATION) AROUND RISER VENT. X 2



- 1. AIR RELEASE VALVES SHALL BE BETWEEN 2-4 FEET BEHIND SIDEWALK.
- 2. COORDINATE WITH GARDNERVILLE WATER COMPANY FOR ASSEMBLY LOCATION TO ALLOW FOR REMOVAL AND REPAIR.
- ALL PIPES SHALL BE SLOPED UP TO AIR RELEASE VALVE. FINISHED GRADE SHALL SLOPE AWAY FROM THE BOX IN ALL DIRECTIONS.
- 4. ALL VALVES SHALL BE BRONZE OR BRASS. ALL PIPES AND FITTINGS SHALL BE BRASS EXCLUDING VENT PIPES.
- 5. STEEL PIPE PAINT SHALL BE RUST-OLEUM 7400 HIGH GLOSS SAFETY YELLOW ALKYD ENAMEL OR GARDNERVILLE WATER COMPANY APPROVED EQUAL.

N	Ο.	REVISION	DATE	GARDNERVILLE WATER COMPANY - STANDARD DETAIL	DRAWING NO.	
	1	GWC REVISIONS	07/24	COMBINATION AIR	G-11	
			VALVE ASSEMBLY	VALVE ASSEMBLY	DATE:	PAGE:
				VALVE AGGLIVIDET	07/24	11